



ADDENDUM NO. 2

S CENTURY DR/HUNTINGTON RD INTERSECTION IMPROVEMENTS

The Bidding Documents for the S CENTURY DR/HUNTINGTON RD INTERSECTION IMPROVEMENTS project are amended as follows:

SPECIAL PROVISIONS

- ***Subsection 01012.40 of the Special Provisions in the original Bidding Documents is replaced with the following:***

01012.40 General - Construct water quality biofiltration swale facility as shown. Perform excavation, fine grading, and placement work only when the facility area is dry and only from the top of the swale area. Do not stockpile excavated material in the facility area. Perform work in sequence as follows:

- (a) **Scarify** - Scarify the subsoil area a minimum 12 inches deep.
- (b) **Placement of Water Quality Mixture** - Place the water quality mixture in maximum 12 inch Lifts. Compact each Lift with a water filled landscape roller.
- (c) **Rock Mulch** - Install rock mulch according to 001040.20.
- (d) **Seeding** - Seed according to 01030.13.

SCHEDULE OF BID ITEMS

- ***The Schedule of Bid Items in the original Bidding Documents is replaced with the attached Schedule of Bid Items.***

The updated Schedule of Bid Items changes the Unit for Bid Item No. 035 – “12 inch Concrete Surfacing, Colored from EACH to SQFT.

The Bidding Documents for the S CENTURY DR/HUNTINGTON RD INTERSECTION IMPROVEMENTS project are amended as described above.

Cody Smith, PE
County Engineer/Assistant Director

September 17, 2025
Date

THIS ADDENDUM, EXCLUDING ATTACHMENTS, SHALL BE SIGNED AND SUBMITTED WITH THE BID PROPOSAL BY THE BIDDER.

I acknowledge receipt of Addendum No. 2.

BIDDER NAME

SIGNATURE OF BIDDER

Date

ITEM NO.	SPEC SECTION	ITEM	UNIT	QTY	UNIT PRICE	AMOUNT
<u>Part 00200 - Temporary Features and Appurtenances</u>						
001	00210	Mobilization	LS	1	\$	\$
002	00221	Temporary Work Zone Traffic Control, Complete	LS	1	\$	\$
003	00223	Automated Flagger Assistance Device	EACH	2	\$	\$
004	00230	Construct and Remove Temporary Roadbed and Surfacing	LS	1	\$	\$
005	00280	Erosion Control	LS	1	\$	\$
007	00280	Sediment Fence	FOOT	1870	\$	\$
008	00280	Concrete Washout Facility	EACH	2	\$	\$
009	00290	Pollution Control Plan	LS	1	\$	\$
<u>Part 00300 - Roadwork</u>						
010	00305	Construction Survey Work	LS	1	\$	\$
011	00310	Removal of Surfacing	SQYD	1780	\$	\$
012	00310	Asphalt Pavement Sawcutting	FOOT	110	\$	\$
013	00310	Removal of Structures and Obstructions	LS	1	\$	\$
014	00320	Clearing and Grubbing	LS	1	\$	\$
015	00330	General Excavation	CUYD	3250	\$	\$
016	00331	12 Inch Subgrade Stabilization	SQYD	150	\$	\$
017	00350	Subgrade Geotextile	SQYD	5500	\$	\$
018	00350	Subgrade Reinforcement Geogrid	SQYD	5500	\$	\$
019	00390	Loose Rip Rap, Class 50	CUYD	15	\$	\$
<u>Part 00400 - Drainage and Sewers</u>						
020	00445	12 Inch Storm Sewer Pipe C900 PVC, 5 FT Depth	FOOT	157	\$	\$
021	00470	Concrete Inlets, Type G-2	EACH	4	\$	\$
<u>Part 00600 - Bases</u>						
022	00641	Aggregate Base	TON	4620	\$	\$
023	00641	Aggregate Shoulders	TON	550	\$	\$
<u>Part 00700 - Wearing Surfaces</u>						
024	00744	Level 3, 1/2" ACP Mixture	TON	2620	\$	\$
025	00749	Extra for Asphalt Approaches	EACH	1	\$	\$
026	00759	Concrete Curbs, High Strength Wide Modified	FOOT	240	\$	\$
027	00759	Concrete Curbs, High Strength Low Profile Mountable, Truck Apron	FOOT	340	\$	\$
028	00759	Concrete Curbs, High Strength Low Profile Mountable	FOOT	2730	\$	\$
029	00759	Concrete Walks	SQFT	545	\$	\$
030	00759	Extra for New Curb Ramps	EACH	12	\$	\$
031	00759	Truncated Domes on New Surfaces	SQFT	230	\$	\$
032	00759	6 Inch Concrete Surfacing	SQFT	34	\$	\$
033	00759	6 Inch Concrete Surfacing, Colored	SQFT	7600	\$	\$
034	00759	8 Inch Concrete Surfacing, Colored	SQFT	3980	\$	\$
035	00759	12 Inch Concrete Surfacing, Colored	SQFT	60	\$	\$
036	00759	Concrete Drainage Apron	EACH	2	\$	\$

ITEM NO.	SPEC SECTION	ITEM	UNIT	QTY	UNIT PRICE	AMOUNT
<u>Part 00800 - Permanent Traffic Safety and Guidance Devices</u>						
037	00840	Delineators, Type 1	EACH	26	\$	\$
038	00855	Bi-Directional Yellow Type IAR Markers, Recessed	EACH	50	\$	\$
039	00856	Permanent Surface Mounted Tubular Markers	EACH	41	\$	\$
040	00865	Thermoplastic, Extruded or Sprayed, Surface, Non-Profiled	FOOT	5824	\$	\$
041	00867	Pavement Legend, Type B-HS: Bicycle Lane Stencil	EACH	3	\$	\$
042	00867	Pavement Bar, Type, B-HS	EACH	432	\$	\$
043	00867	Pavement Legend, Type, B-HS: Yield Line Triangle	EACH	18	\$	\$
044	00867	Pavement Legend, Type B-HS: Transverse Speed Reduction Marker	EACH	70	\$	\$
<u>Part 00900 - Permanent Traffic Control and Illumination Systems</u>						
045	00905	Remove Existing Signs	LS	1	\$	\$
046	00905	Remove and Reinstall Existing Signs	LS	1	\$	\$
047	00920	Sign Support Footings	LS	1	\$	\$
048	00930	Perforated Steel Square Tube Slip Base Sign Supports	LS	1	\$	\$
049	00940	Signs, Standard Sheeting, Sheet Aluminum	SQFT	200	\$	\$
050	00970	Pole Foundations	LS	1	\$	\$
051	00970	Conduit, Pull Ropes and Junction Boxes	LS	1	\$	\$
<u>Part 01000 - Right of Way Development and Control</u>						
052	01012	Water Quality Mixture	CUYD	520	\$	\$
053	01030	Permanent Seeding	ACRE	1.8	\$	\$
054	01040	Conifer Trees, 5-6 ft height	EA	7	\$	\$
055	01040	Topsoil	CY	7	\$	\$
056	01040	Rock Mulch	CY	250	\$	\$
057	01040	Three Man Boulders	EA	9	\$	\$
058	01070	Single Mailbox Support	EA	1	\$	\$
					TOTAL BID:	\$

FOR DESCHUTES COUNTY USE ONLY

ADD _____ % FOR NON-RESIDENT BIDDER

TOTAL BID